



### Installation Procedure

Watson Bowman Acme Corp. 95 Pineview Drive Amherst, NY 14228 phone: (716) 691-7566 fax: (716) 691-9239

website: www.wbacorp.com

Information provided herein, including but not limited to, any drawing, design, photograph, graphic, or statement(s) ("Materials") are proprietary and the property of Watson Bowman Acme Corporation ("Company"). Reproduction, translation, or reduction to any electronic medium or machine readable form, in whole or part, is strictly prohibited, except for the express purpose for which it has been furnished, without prior written consent of Company. All Materials contained herein are provided by Company for information purposes only. Company reserves the right to amend or withdraw any information contained in the Materials without notice. All technical or other advice by Company, whether verbal or written, concerning products, or the use of products in specific situations ("Advice") is given by Company and is used at the Users own risk.





2 Layers 4" thru 6" 3 Layers 8" thru 12"


# Wabo® FlameGuard II - Life Safety Series Model(s) "UFG" & "UFG Corner" 4"-12" Horizontal Fire Barrier Systems

The following installation procedure is very important and must be fully understood prior to beginning any work. To ensure proper installation and performance of expansion joint system the following actions must be completed by the installing contractor. Failure to do so will affect product warranty and fire barrier performance.

- 1) Carefully read and understand installation procedure. Contact WBA's Technical Service Department at (800) 677-4922 for product assistance.
- 2) Inspect all shipments and materials for missing or damaged components and hardware. Contact Customer Service at (800) 677-4922 with WBA's order number and invoice for prompt assistance.
- Inspect substrate or adjacent construction for acceptance before beginning work. Report unacceptable construction to the project manager for scheduled repair work.
- 4) Review WBA shop drawings for project specific detailed information if Engineering services were purchased at time of order.


Issued: 12/8/06 p/n: 20246

### Standard Components For Floor Condition




Flameguard II 8" thru 12" Floor Assembly (For size and p/n refer to chart)

Model #	Part # 1 hr	Part # 2 hr
UFG-1201,1202	UFG1201	UFG1202
UFG-1001,1002	UFG1001	UFG1002
UFG-801,802	UFG801	UFG802




Flameguard II 4" thru 6" Floor Assembly (For size and p/n refer to chart)

Model #	Part # 1 hr	Part # 2 hr	
UFG-601,602	UFG601	UFG602	
UFG-401,402	UFG401	UFG402	




Splice Transition (For size and p/n refer to chart)

Model #	Part #
UFG-1201,1201C,1202,1202C	3211
UFG-1001,1001C,1002,1002C	3211
UFG-801,801C,802,802C	3208
UFG-601,601C,602,602C	3206
UFG-401,401C,402,402C	3204



1/4" Flat Washer Part Number - 7473



Flameguard II 8" thru 12" Corner Assembly (For size and p/n refer to chart)

Model #	Part # 1 hr	Part # 2 hr
UFG-1201C,1202C	UFG1201C	UFG1202C
UFG-1001C,1002C	UFG1001C	UFG1002C
UFG-801C.802C	UFG801C	UFG802C



Flameguard II 4" thru 6" Corner Assembly (For size and p/n refer to chart)

Model #	Part # 1 hr	Part # 2 hr UFG602C	
UFG-601C,602C	UFG601C		
UFG-401C,402C	UFG401C	UFG402C	

Components shown below vary in size depending on model of system


Sheet 1 of 5

> Watson Bowman Acme Corp. 95 Pineview Drive Amherst, NY 14228 phone: (716) 691-7566 fax. (716) 691-92 webisite: www whacom com

"UFG" FlameGuard II system


nstallation procedure: "UFC

Installat
Information provided herein, including
Corporation ("Company"). Reproduction
which it has been furnished, without pric
amend or withdraw any information cont




Prepare concrete block out for installation of fire barrier. Deficiencies in block out base and spalled edges must be corrected prior to beginning work.

Note: Contractor to repair any spalled edges with a Repair Material approved by the Buildings Structural Engineer.



Refer to WBA shop drawings to determine depth of Splice transition.

Mark fire barrier splice locations and outline edges of splice transition as shown.




After splice locations have been determined, secure splice transition utilizing duct tape to concrete slab as shown in photo.

Sheet

Watson Bowman Acme Corp. 95 Pineview Drive Amherst, NY 14228 ne: (716) 691-7566 fax: (716) 691-92: Website: Www.wbacorp.com

system FlameGuard II procedure nstallation






4

Insert 10' section of fire barrier into opening. Ensure that end of fire barrier is located on centerline of Splice Transition. Once fire barrier is inserted into opening, mount wood blocking insert and wedge wood spreader to expend fire barrier to its correct position.


#### Notes:


1. Wood blocking and spreader is required to ensure that fire barrier is installed tight to adjacent concrete construction.



## Wood Blocking

Required only when system incorporates third Fire Barrier Blanket outside of metal retainer as shown in photo above. Not required if third blanket is not used.





***************************************	Model	"A"	"T"
	UFG-1201,1201C,1202,1202C	10"	1"
	UFG-1001,1001C,1002,1002C	8"	1"
	UFG-801,801C,802,802C	6"	1"
ſ	UFG-601,601C,602,602C	4"	1"
ſ	UFG-401,401C,402,402C	2"	1"


Sheet

Watson Bowman Acine Corp. 5 Pineview Drive Amherst, NY 14228 : (716) 691-7566 fax: (716) 691-9239 Website: www.wbacorp.com


FlameGuard II system "UFG"

procedure nstallation






Once fire barrier has been blocked open, mark and drill holes for 1/4" x 2 1/4" lg concrete sleeve anchors spaced at 9" O.C. Once the holes have been drilled, remove powder dust exercising care not to get debris into fire blanket assembly. Install concrete sleeve anchor with washers.



1/4" Concrete Sleeve Anchor & washer Spaced at 9" O.C. (Minimum 14 anchors per 10ft length of fire barrier - each side)

Once fire barrier has been blocked open, mark and drill holes for 1/4" x 2 1/4" lg concrete sleeve anchors spaced at 9" O.C. Once the holes have been drilled, remove powder dust exercising care not to get debris into fire blanket assembly. Install concrete sleeve anchor with washers.



1/4" Concrete Sleeve anchor and washer

6

After the first section of fire barrier has been installed, apply CP601S sealant to all blanket layers of the fire blanket assembly(Except: slice transition).


Sheet of 5

Watson Bowman Acme Corp. 5 Pineview Drive Amherst, NY 14228 : (716) 691-7566 fax: (716) 691-9239 Website: www.wbacorp.com

system FlameGuard

procedure nstallation

Splice Line (No Gaps)



7

Repeat Step 4 with next section of fire barrier. Install next section ensuring that there are no gaps at the splice location between blankets, as shown above.

#### Note:

To remove small gaps between sections of fire barrier gently tap opposite ends of metal retainers with a hammer and wood blocking to slowly move the fire barrier forward compressing the CP601S sealant at the splice line. Exercise care not to damage fire barrier blanket where wood blocking is applied.

8

After the next fire barrier section is in place, repeat step 5A or 5B.

9

With installation complete temporarily cover system to ensure debris does not enter fire barrier cavity. It shall be the installers responsibility to protect completed fire barrier installations. Damaged Fire Barriers will be replaced at installers expense.

Sheet 5 of 5

Watson Bowman Acme Corp.
95 Pineview Drive Amherst, NY 14228
phone: (716) 691-7566 fax: (716) 691-9239
WebSite: www.wbacorp.com

"UFG" FlameGuard II system

Installation procedure: "UFG" I

Information provided herein, including but not limited to any drawing, design, photograph, graphic, or statement(s) (Materials') are proprietty and Corporation ("Company"). Reproduction, translation, or reduction to any electronic medium or machine rescabble form, in whole or part, is startly profit with thas been furnished, whout prior wither or Company. All Materials contained herein are provided by Company for information purp amend or withdraw any information contained in the Materials without notice. All technical or other advice by Company wither over

Watson Bouman Acme